



**Advanced Indirectly Heated  
Carbonate Looping Process**



# ANICA Project

Jochen Ströhle, TU Darmstadt

ACT Knowledge Sharing Workshop  
9 June 2022



Federal Ministry  
for Economic Affairs  
and Energy



Department for  
Business, Energy  
& Industrial Strategy




**GERT**  
GENERAL SECRETARIAT FOR  
RESEARCH AND TECHNOLOGY

This project ANICA is funded through the ACT programme (Accelerating CCS Technologies, Horizon2020 Project No 294766). Financial contributions made from the German Federal Ministry of Economic Affairs and Energy, the Department for Business, Energy and Industrial Strategy of the United Kingdom and the Greek General Secretariat for Research and Technology.


## Overall aim:

*Develop concepts of indirectly heated carbonate looping (IHCaL) process for **CO<sub>2</sub> capture** from **lime** and **cement** plants.*



## Specific Project Objectives


- Test at 300 kW<sub>th</sub> **pilot plant**
- Prove feasibility of **utilizing of spent sorbent**
- Develop **novel concepts** of IHCaL reactors
- Assess **risks, economics, environmental** impact
- Design a 20 MW<sub>th</sub> **demonstration** plant



Source: Lhoist




# Indirectly Heated Carbonate Looping (IHCaL)




- Sorbent (limestone): cheap, abundant, non-toxic, environmentally friendly
- Spent sorbent (CaO): utilization in lime/cement production
- Utilization of heat at high temperature (→ highly efficient steam cycle)
- No oxygen for calciner → No ASU, **high efficiency**
- No fuel in calciner → **few impurities** (sulfur, ash), **low deactivation**
- Almost **pure CO<sub>2</sub>** stream at calciner exit

# KPIs for Lime/Cement Plants





Key Performance Indicator (KPI)	Target
CO <sub>2</sub> capture efficiency	> 90 %
CO <sub>2</sub> purity	> 95 %
Net efficiency for power co-generation	> 45 %
Sorbent utilization	> 90 %
CO <sub>2</sub> avoidance costs	< 25 €/t
Net CO <sub>2</sub> emissions	< 0




# WP 1 – Process Development

- Process design and simulation completed
  - Integration into lime and cement plants
  - High potential for power recovery: > 30%
  - Over 85% CO<sub>2</sub> avoidance
  
- Challenges:
  - Reactivity/PSD of cement raw meal
  - Heat integration and operation set-point
  - Component development




## WP 2 – Pilot Testing


- All construction works at 300 kW<sub>th</sub> pilot plant completed



- Successful completion of first pilot test with real flue gas



- Solid samples generated for assessment of usability in lime and cement





- Next pilot tests in Summer 2022 with solid fuels and cement raw meal







# WP 3 – Reactor Development

- Reactor models developed
- Lagrangian-Eulerian CFD model of pilot plant validated



- Assessment of 4 concepts for a solid/solid heat exchanger completed
- Development of improved heat pipes in progress



- Risk assessment (in progress)
  - Quantitative risk assessment (Monte Carlo)
  - Qualitative risk assessment (FMECA)

Description of the unit			Description of the failure			Effect of the failure				Probability of occurrence	Risk Priority Number <small>Rodif severity x probability &gt; 9</small>	Risk reducing measures	Comments
Component	Function	Operational Mode	Failure mode	Failure cause or mechanism	Difficulty of detection	On the component	On the system	Health & Safety	Severity ranking				
					1 to 5				1 to 5	1 to 5			

- Techno-economic assessment (in progress)
  - Preliminary CO<sub>2</sub> avoidance costs for cement plant:
    - 24.3 €/t (30% SRF)
    - 36.4 €/t (100% coal)



- Life-cycle assessment (in progress)
  - Large reduction on global warming impact
  - Use of SRF is beneficial





- Combination of IHCaL with Direct Separation (CALIX)
- Several Scenarios defined
- Heat & mass balances in progress


# WP7 – Dissemination and Exploitation




[www.act-anica.eu](http://www.act-anica.eu)



ANiCA Project Website



4 Industrially Oriented Newsletters



Public workshop  
6 Oct 2022 (online)

9 conference presentations  
1 journal paper


# Next Steps in ANICA



Pilot tests  
(Jan – Aug 2022)





Analysis of sorbents  
→ utilization in  
production process




Model  
validation

## Process optimization (novel reactor concepts, simulations)



Design of  
demonstration  
plants



Process assessment  
(risks, economics,  
environmental impact)



The project has been subsidized through ACT (Project no. 299653, ANICA) by the German Federal Ministry of Economic Affairs and Energy based on a resolution of the German Parliament under grant no. 03EE5025, the Department for Business, Energy and Industrial Strategy of the United Kingdom under grant agreement 691712, and the Greek General Secretariat for Research and Technology.

Supported by:



on the basis of a decision  
by the German Bundestag

Thank you for your attention!

